# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2012-13/RD/WORK_INDENT4582/CALL-2

## APPROVED SCHEDULE - B

**No.EE/BTP/BBMP/E-PMT/05/2014-15, Date:17.07.2014**

**Improvements to Roads, Drains in BGS layout in ward no. 7, Byatarayanapura**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of PRATAP | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 1191.3 | Removing BS Slab of drain and stacking. | Sqm | 52.61 | Rupees Fifty Two and Sixty One Paise Only |
| 2 | 953.04 | Refixing stone slabs of drains and pointing in CM 1:3. | Sqm | 73.53 | Rupees Seventy Three and Fifty Three Paise Only |
| 3 | 238.26 | Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick) | Sqm | 360.58 | Rupees Three Hundred Sixty and Fifty Eight Paise Only |
| 4 | 476.1 | KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3. | Cum | 69.17 | Rupees Sixty Nine and Seventeen Paise Only |
| 5 | 3728 | KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (167, I.No. 19.64) SR 2012-13 | Cum | 4.25 | Rupees Four and Twenty Five Paise Only |
| 6 | 260.1 | KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 167, Item No. 20.18) SR 12-13 | Cum | 1176.98 | Rupees One Thousand One Hundred Seventy Six and Ninety Eight Paise Only |
| 7 | 1734 | KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 172, Item No. 21.6) SR 12-13 | Sqm | 46.49 | Rupees Forty Six and Forty Nine Paise Only |

| | | | | | |
|---|---|---|---|---|---|
| 8 | 43.35 | KSRRB M500-18. Providing and laying semi dense bituminous concrete 25 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver (P. 174, Item No. 21.20.5) SR 12-13 | Cum | 10112.05 | Rupees Ten Thousand One Hundred Twelve and Five Paise Only |

H.R.

**Signature of the Contractor**

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore - 92**